



Office of the Executive Engineer
Road Construction Department, Road Division, Sahibganj

Corrigendum No. 2 (PR. No.-131714)

Tender Reference No. : RCD/SAHIBGANJ/1311/2015-16 (2nd Call)
 Name of the Work : Widening and Strengthening of NH-80 from K.M. 196.00 to 225.00
 (Mirzachouki-Karamtola-Sahibganj-Balapokhar-Maharajpur) under
 Road Division, Sahibganj

Corrigendum Title : **(1) Change in specification in description of work,
 Sl. No. 13, Sl. No. 18 and Sl. No. 19
 (2) Change in Bid Value and Bid Security Value
 (3) Change in Bid Submission Date
 (4) Change in Sl. No. 3, 4 and 8 of Appendix to ITB**

Corrigendum Details :

01. Section 7 of ITB Title “Bill of Quantity”, Sl. No. 13, 18 and 19

Sl. No.	As Published	To be read as
13.	Construction of subgrade by providing, laying, spreading and compacting stone dust of specified in uniformed layers on a prepared surface with motor grader and compacting with power roller complete job as per direction of E/I.	Construction of subgrade with approved materials (65% earth + 35% stone dust) obtained from borrow pits with all lifts and leads, transporting to site, spreading, grading t required slope and compacted earthwork to meet the requirement of table 300-2
18.	Providing and laying dense graded bituminous macadam with 100-120 TPH batch type HMP producing an average output of 75 tonnes per hour using crushed aggregates of specified grading, premixed with bituminous binder @ 4.0 to 4.5 per cent by weight of total mix and filler, transporting the hot mix to work site, laying with a hydrostatic paver finisher with sensor control to the required grade, level and alignment, rolling with smooth wheeled, vibratory and tandem rollers to achieve the desired compaction as per MoRTH specification	Providing and laying dense graded bituminous macadam with 100-120 TPH batch type HMP producing an average output of 75 tonnes per hour using crushed aggregates of specified grading, premixed with bituminous binder @ 4.0 to 4.5 per cent by weight of total mix and filler, transporting the hot mix to work site, laying with a hydrostatic paver finisher with sensor control to the required grade, level and alignment, rolling with smooth wheeled, vibratory and tandem rollers to achieve the desired compaction as per MoRTH specification clause No. 507 complete in all respects with VG-30 grade bulk

	clause No. 507 complete in all respects. Grade-I NHSOR 5.6 (i)	bitumen. NHSOR 5.6 B (i)
19.	Providing and laying bituminous concrete with 100-120 TPH batch type hot mix plant producing an average output of 75 tonnes per hour using crushed aggregates of specified grading, premixed with bituminous binder @ 5.4 to 5.6 per cent of mix and filler, transporting the hot mix to work site, laying with a hydrostatic paver finisher with sensor control to the required grade, level and alignment, rolling with smooth wheeled, vibratory and tandem rollers to achieve the desired compaction as per MORTH specification clause No. 509 complete in all respects. Grade-II NHSOR 5.8 ii	Providing and laying bituminous concrete with 100-120 TPH batch type hot mix plant producing an average output of 75 tonnes per hour using crushed aggregates of specified grading, premixed with bituminous binder @ 5.4 to 5.6 per cent of mix and filler, transporting the hot mix to work site, laying with a hydrostatic paver finisher with sensor control to the required grade, level and alignment, rolling with smooth wheeled, vibratory and tandem rollers to achieve the desired compaction as per MORTH specification clause No. 509 complete in all respects with VG-30 bulk bitumen. NHSOR 5.8 B (ii)

02. In the Sl. No. 1, Column 3 and 4 as well as Sl. No. 2, Column 8 and 9 of Invitation for Bids (IFB)

Sl. No.	As published	To be read as
Sl. no. 1 Column 3 of IFB (appropriate value of work)	Rs. 5591.2591 lacs	Rs. 5605.66 lacs
Sl. no. 2 Column 4 of IFB (Bid Security)	Rs. 55.92 lacs	Rs. 56.06 lacs
Sl. no. 2, Column 8 of IFB via corrigendum (last date of bid submission)	16.11.2015	27.11.2015
Sl. no. 2, Column 9 of IFB via corrigendum (date of opening of technical bid)	19.11.2015	30.11.2015

03. In Sl. no. 3, 4 and 8 of Appendix to ITB clause reference with respect to Section-1

Sl. No.	As published	To be read as
Sl. no. 3 Cl. 4.5A (a) (Annual Financial Turn Over)	Rs. 8386.88 lacs	Rs. 8408.49 lacs
Sl. no. 4 Cl. 4.5 A (b) (Value of Work)	Rs. 2795.63 lacs	Rs. 2802.83 lacs
Sl. no. 8, Cl. 4.5 B (c) Liquid assets/availability of credit facility	Rs. 1397.814 lacs	Rs. 1401.41 lacs

04. In Sl. no. 23 and 38 of Contract Data, Clause reference with respect to Section-3, Condition of Contract.

Sl. No.	As published	To be read as
Sl. no. 23 Cl. 27.3 (Amount to be withheld for late submission of an updated programme)	Rs. 13.97 lacs	Rs. 14.01 lacs
Sl. no. 38, Cl. 58 (Amount withheld for failing to supply "as built" drawings by date required)	Rs. 27.95 lacs	Rs. 28.02 lacs

Note : Other Conditions remain unchanged.

Executive Engineer
Road Construction Department
Road Division, Sahibganj

PR No: 133031(Road)

Published On: 20/11/2015